

BULLETIN NO. 100108

DATE: January 8, 2010

PRODUCT: Dunkirk PWXL Boilers

FROM: Technical Service Department

TITLE: Transformer Replacement

MODELS AFFECTED

| |
|---|
| PWXL – all sizes Spark and Standing Pilot |
|---|

SERIAL NO. RANGE: All manufactured units.

SITUATION

Replacement of Factory-Installed Transformer requires the use of OEM Parts Only! This is not a standard transformer. It has two sets of secondary windings. It is made particularly for the Hydrolevel control and has two sets of secondary transformer leads. Replacement using any standard transformers will result in Hydrolevel Aquastat control failure. See photos 1 and 2.

SOLUTION

Dunkirk highly recommends wholesalers stock the following replacement parts.

| Part Number | Description | Where Used |
|--------------------|--------------------------------------|-----------------------------|
| 240007710 | Hydrolevel Combination Aquastat/LWCO | Used in all sizes. |
| 240007897 | Transformer | Used in all sizes. |
| 240007708 | Sensor - 48" lead | Used in 3-5 section boilers |
| 240007909 | Sensor - 60" lead | Used in 6-9 section boilers |

TECHNICAL BULLETIN




PHOTO 1



PHOTO 2

If you have any questions regarding information contained in this bulletin please contact ECR Technical Service at 1-800-325-5479.